

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

For corners in

SECTION

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T22N R02E</u>	<u>M-3</u>
	<u>T22N R3E</u>	<u>A-3</u>
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property In Sec.	S T R	
	S T R	



**3006794**  
Page: 1 of 1  
12/27/1999 09:09A  
L-4 P-3  
Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

M-3: GLO by L. Clason, 1836, Post  
A-3 N23W 61 20" Hemlock  
S27W 19 10" Hemlock

LCRC by T. Lapham, 1987, Found 1/2" capped iron  
N45W 102.70 SE Cor brick 2 story house  
S33E 72.95 Power Pole  
N75E 79.04 Gas Line Marker  
S50E 62.08 Engle Road Sign

Consumers Power Survey, 1965+-, Found Pk nail  
SW 58.6 Fence Post  
SE 72.9 Power Pole  
SE 40.0 Rd Sign Post  
NE 58.0 Gas Line Marker

Approved by Peer Review

12-16-99  
DATE

WFL  
INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3: No GLO evidence found. Found 1/2" iron, 1 - 1965 witness, and 3 - 1987 witnesses. Distance to M/A-1 and M/A-5 match 1965 survey accepted found iron  
A-3 as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3: Set 5/8" rerod w/aluminum remon cap  
A-3 N45W 102.70 SE Cor brick 2 story house  
S33E 72.95 Utility Pole  
N75E 79.04 Gas Line Marker  
N35W 123.27 NE Cor brick 2 story house  
West 1.0 Centerline M-33

Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/23/1999