

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

SECTION _____

For corners in

Ogemaw Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T22N R02E M-4
 T 22NR 03E A-4
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 In Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____



3006793
 Page: 1 of 1
 12/27/1999 09:09A
 L-4 P-2
 Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- GLO by L. Clason, 1838, Post box
- N34W 25 k 18" Hemlock NW 88.55 24" Oak
- S64W 34 k 9" Beech NE 88.39 Power Pole
- SE 88.69 Gas Pipeline Marker
- Survey by R. Higgins, 1976, Found pvmt box SW 67.70 Power Pole
- East 0.9 Centerline East 0.9 Const Centerline Joint
- Survey by R. Higgins, 1976, Found iron in pvmt box Survey by L. Cavanagh, 1974, No material
- East 0.9 Centerline M-33 Shown at centerline roads
- Survey by N. Caldwell, 1979, No material Survey by N. Caldwell, 1975, No material
- Survey by D. Ledy, 1984, Found 1/2" rod in mon Consumers Power Survey, 1985+-, Found Pk nail
- box NW 88.72 24" Oak
- NW 88.55 24" Oak NE 88.15 Power Pole
- NE 88.39 Power Pole SE 88.56 Hwy Marker
- SE 88.69 Gas Pipeline Marker (top canter)
- SW 67.70 Power Pole
- Survey by D. Ledy, 1985, Found 1/2" rod in mon

Approved by Peer Review
12-16-99 JLF
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No GLO evidence found. Found 1/2" capped iron in monument box. Found 2 - 1985 witnesses and distances North and South match 1985 survey distances. Also found 1 - 1976 witness, 4 - 1984 witnesses, and 1 - 1985 witness. Accepted found iron as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" rerod w/aluminum remon cap
 N46W 88.75 28" Oak
 S57E 88.70 Top of Pipeline
 S53W 87.55 Utility Pole
 N58E 88.43 Utility Pole

Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/23/1999