

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

SECTION

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R02E T22N R03E T ___ R ___ T ___ R ___	M-6 A-6 _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____



3006796
 Page: 1 of 1
 12/27/1999 09:09A
 L-4 P-5
 Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO by L. Clason, 1838, Post
N41W 34 lks 12" Beech
S34W 9 lks 12" Beech
- LCRC by R. Higgins, 1982, Found PK Nail
East 74.13 Spike in top of fence corner post
S21°44'E 34.51 Spike
NE 152.42 Pass with care sign post
West 8.5 Centerline of corner
- Survey by N. Caldwell, 1980, No material
Corner by Higgins
- Consumers Power Survey, 1965+-
Corner not set

Approved by Peer Review
12-16-99 JSL
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No GLO evidence of corner found. Found Pk nail and 3 - 1982 witnesses. Nail is very close to midway on line between M/A-5 and M/A-7. Accepted found nail as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"x36" rod w/aluminum remon cap
- S30E 96.02 12' Oak
- West 9.07 Centerline M-33
- East 74.13 Top Fence Cor Post
- N10W 400.30 Survey Control Marker

Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/23/1999