

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

For corners in

<u>Ogemaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T22N R02E T22N R03E T____R____ T____R____	M-7 A-7 _____ _____
2. Property Controlling in Section	S____T____R____ S____T____R____	_____ _____
3. Miscellaneous Property In Sec.	S____T____R____ S____T____R____	_____ _____

SECTION



3006788
 Page: 1 of 1
 12/27/1999 09:09A
 L-3 P-297
 Wanda Muzik, Ogemaw Co. Register SURC 9.00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:**
- GLO by L. Clason, 1838, Post
N43W 45 12' Beech
S80W 48 12' Hemlock
Sta = 52+62.8
 - Consumers Power Survey, 1965+-
Set Pk nail per highway station
NW 56.20 Hwy Marker
SE 57.25 Hwy Marker
NE 55.24 Steel Fence Post
 - LCRC by R. Higgins, 1982, Pavement Box
NW 56.20 Hwy Marker
NE 55.24 Steel Fence Post
SE 76.45 Set Spike in top center post guard rail
SW 38.34 Set spike in top center post of guard rail
 - Survey by N. Caldwell, 1980, No material
 - Survey by T. Lapham, 1996, Found pavement box
NW 56.20 Highway Marker
NE 55.24 Steel Fence Post
SE 76.45 Guard Rail Post
SW 38.34 Guard Rail Post
 - MDOT Road Plans, No Material
No corner set

Approved by Peer Review
12/23/99 JLF
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No GLO evidence found. Found 1/2" capped iron in monument box. Distances North and South match 1965 distances. No previous witnesses found. Accepted found iron as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8"x36" rerod w/aluminum remon cap
 N46E 70.74 Utility Pole
 S15E 78.10 Guard Post
 S41W 39.83 Guard Post
 N80W 56.78 Tele Ped Post
 West 0.7 Centerline M-33



Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/23/1999