

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

SECTION

For corners in

Ogemaw (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R02E	M-9
	T 22N R 03E	A-9
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	



3006801
 Page: 1 of 1
 12/27/1999 09:09A
 L-4 P-10
 Handa Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO by L. Clason, 1838, Post
 - N26W 21 lks 20" Hemlock
 - S82W 31 lks 9" Hard Maple
- LCRC by J. Nelson, 1988, Found 3/8" rerod in mon box
 - Az 49° 76.27 Power Pole
 - Az 153° 103.77 Michcon Aerial Mrk, 16" pipeline
 - Az 230° 76.56 Power Pole
 - Az 307° 113.19 Power Pole
- LCRC by T. Lapham, 1993, Found 1/2" iron in mon box
 - N60W 113.10 Power Pole
 - N45E 76.59 Power Pole
 - S50W 78.19 Power Pole

- N45E 76.59 Power Pole
- S50W 78.19 Power Pole
- Consumers Power Survey, 1965+-, Found monument box
 - NE 76.18 Tele Pole
 - SE 73.35 Rd Marker
 - SW 62.34 Stub Pole
 - NW 113.5 Power Pole

Survey by N. Caldwell, 1973, No material

Survey by T. Lapham, 1997, Found Iron
 N60W 113.10 Power Pole

Approved by Peer Review

12-16-99 DATE JNL INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No GLO evidence found. Found 3/4" iron in monument box at intersection centerlines of M-33 and M-55. Found 2 - 1965 witnesses, 3 - 1988 witnesses (2 witness distances appeared to be switched) and 3 - 1993 witnesses. Distances North and South 1 mile match 1965 survey. Accepted found iron as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"x36" rerod w/aluminum remon cap
 - N45E 76.59 Utility Pole
 - S30W 95.18 Horz Control Mark
 - S50W 78.19 Utility Pole
 - N60W 113.10 Utility Pole

Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/23/1999