

**Ogemaw County Remonumentation**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RIP  
 FEB 24 2000

FEB 24 2000

SECTION

for corners in \_\_\_\_\_

Ogemaw Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

Public Land Survey T22N R02E M-12  
 T22N R03E A-12  
 T R \_\_\_\_\_  
 T R \_\_\_\_\_

Property Controlling S T R \_\_\_\_\_  
 In Section S T R \_\_\_\_\_

Miscellaneous S T R \_\_\_\_\_  
 Property in Sec. S T R \_\_\_\_\_



**3006790**  
 Page: 1 of 1  
 12/27/1999 09:09A  
 L-3 P-299  
 Wanda Muzik, Ogemaw Co. Register SURC 9.00

**Register of Deeds Stamp & File Number**

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, discovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

**Description of original monument and accessories and/or subsequent restoration:**

- GLO by L. Clason, 1838, Post West 3 Centerline M-33  
 N48W 65 16" Hemlock  
 S24W 22 12" S Maple
- MDOT Road Plans, No material  
 West 2.82 Centerline M-33  
 Sta 442+07.15
- Consumers Power Survey, 1965+-  
 Corner not set
- LCRC by C. Lindgren, 1989, Set 1/2" rod and cap, Stamped MDOT 14098  
 N50E 78.38 6" Oak  
 East 29.83 Top Wood Guard Post  
 S30E 50.28 Top Wood Guard Post  
 N85W 35.27 Top Wood Guard Post
- Survey by J. May, 1998, Found MDOT iron in mon box  
 N50E 78.38 6" Oak  
 East 29.83 Top Wood Guard Post  
 S30E 50.28 Top Wood Guard Post  
 N85W 35.27 Top Wood Guard Post
- Survey by D. Ledy, 1990, Found 1/2" rod and cap  
 East 29.87 Top Guard Rail Post  
 SE 50.33 Top Guard Rail Post  
 West 35.3 Top Guard Rail Post

Approved by Peer Review

12-16-99 SLR  
 DATE INITIALS

**Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of GLO corner found. Found 1/2" capped iron (MDOT) in monument box. Found iron approximately matches stream call to South. MDOT R/W maps calls for corner to be 2.82' East of centerline but MDOT iron is on centerline. Iron is very close to S.P.M. between M/A-11 and M/A-13. Distances North and South very closely match 1965 survey calls. Found 4 - 1989 and 4 - 1990 witnesses. Accepted found iron as carefully established position and best available evidence of correct corner position.

**Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set 5/8"x36" rerod w/aluminum remon cap  
 East 29.35 Top Wood Guard Rail  
 S30E 50.30 Top Wood Guard Post  
 S35W 60.05 Top Wood Guard Post  
 N85W 35.30 Top Wood Guard Post  
 West 3.0 Centerline M-33

Signed by [Signature]  
 Surveyor's Michigan License No. 27595

Date 12/23/99