

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>22</u> N. R. <u>3</u> E.	K-5; K-6; K-7
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 21, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-5 Fd. 4" squared cedar post in fence line North, wired to end fence post. Appears to have been in ground for long period and was removed to set fence post. Best available evidence of proper location for corner.
- K-6 Set corner by proportionate measurement between section corners. - Land all swamp, nothing for previous corner.
- K-7 Set corner by proportionate measurement between corners 1 mile East and 1 mile West, using occupational lines to prescribe latitudinal position. Cannot identify U.S. evidence or a previous corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	K-5	K-6	K-7
Set DNR mon.		Set 1" pipe w/RLS cap	Set 1" pipe w/RLS cap
6" White Pine	S21°E 37.1'	6" Cedar N82°W 11.6'	6" Cedar N30°E 7.7'
12" White Pine	S40°W 14.9'	16" Cedar S24°W 11.8'	6" Cedar S66°E 7.8'

SIGNED BY Kenneth J. Ostling SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 3/12/80



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ OGEMAW COUNTY