

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RF

FEB 24 2000

SECTION

For corners in

Ogemaw
 (County)

Located in:

Corner Code #

1. Public Land Survey

T22N R02E M-4
 T 22N R 03E A-4 ✓

2. Property Controlling
 In Section

S T R
 S T R

3. Miscellaneous
 Property In Sec.

S T R
 S T R



3006793
 Page: 1 of 1
 12/27/1999 09:09A
 L-4 P-2

Manda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- GLO by L. Clason, 1838, Post box
 N34W 25 k 18" Hemlock NW 88.55 24" Oak
 S84W 34 k 9" Beech NE 68.39 Power Pole
 SE 88.69 Gas Pipeline Marker
 Survey by R. Higgins, 1976, Found pvmt box SW 67.70 Power Pole
 East 0.9 Centerline East 0.9 Const Centerline Joint
- Survey by R. Higgins, 1976, Found iron in pvmt box
 East 0.9 Centerline M-33
- Survey by L. Cavanagh, 1874, No material
 Shown at centerline roads
- Survey by N. Caldwell, 1979, No material
- Survey by N. Caldwell, 1975, No material
- Survey by D. Ledy, 1984, Found 1/2" rod in mon box
 NW 88.55 24" Oak
 NE 68.39 Power Pole
 SE 88.69 Gas Pipeline Marker (top center)
 SW 67.70 Power Pole
- Consumers Power Survey, 1965+, Found Pk nail
 NW 88.72 24" Oak
 NE 68.15 Power Pole
 SE 68.56 Hwy Marker
- Survey by D. Ledy, 1985, Found 1/2" rod in mon

Approved by Peer Review

12-16-99 SSP
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No GLO evidence found. Found 1/2" capped iron in monument box. Found 2 - 1965 witnesses and distances North and South match 1965 survey distances. Also found 1 - 1976 witness, 4 - 1984 witnesses, and 1 - 1985 witness. Accepted found iron as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" rerod w/aluminum remon cap
- N46W 88.75 28" Oak
- S57E 88.70 Top of Pipeline
- S53W 67.55 Utility Pole
- N58E 68.43 Utility Pole

Signed by *Timothy L Lapham*
 Surveyor's Michigan License No. 27595

Date 12/23/1999