

Ogemaw County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RF

FEB 24 2000

For corners in

Ogemaw  
 (County)

Located In:

Corner Code #

SECTION

1. Public Land Survey

T22N R02E M-6  
 T22N R03E A-6

2. Property Controlling  
 in Section

S T R

3. Miscellaneous  
 Property in Sec.

S T R  
 S T R



**3006796**  
 Page: 1 of 1  
 12/27/1999 09:09A  
 L-4 P-5  
 Manda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

GLO by L. Clason, 1838, Post  
 N41W 34 lks 12" Beech  
 S34W 9 lks 12" Beech

LCRC by R. Higgins, 1982, Found PK Nail  
 East 74.13 Spike in top of fence corner post  
 S21°44'E 34.51 Spike  
 NE 152.42 Pass with care sign post  
 West 8.5 Centerline of corner

Survey by N. Caldwell, 1980, No material  
 Corner by Higgins

Consumers Power Survey, 1965+-  
 Corner not set

Approved by Peer Review

12-16-99 JSL  
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No GLO evidence of corner found. Found Pk nail and 3 - 1982 witnesses. Nail is very close to midway on line between M/A-5 and M/A-7. Accepted found nail as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod w/aluminum remon cap  
 S30E 98.02 12" Oak  
 West 9.07 Centerline M-33  
 East 74.13 Top Fence Cor Post  
 N10W 400.30 Survey Control Marker

Signed by [Signature]  
 Surveyor's Michigan License No. 27595

Date 12/23/1999