

Ogemaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

or corners in

Ogemaw  
(County)

Located in:

Corner Code #

SECTION

Public Land Survey

T22N R02E M-7  
T22N R03E A-7 ✓  
T R  
T R  
S T R  
S T R  
S T R  
S T R

Property Controlling  
in Section  
Miscellaneous  
Property in Sec.

3006788  
Page: 1 of 1  
12/27/1999 09:09A  
L-3 P-297  
Manda Muzik, Ogemaw Co. Registrar SURC 9.00

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

Timothy L Lapham, in a field survey on December, 19 99 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in  
the current manual of survey instructions of the United States Department of the Interior,  
Bureau of Land Management or by a decree of a Court of Law and/or that the corner points  
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board  
of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,  
discovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2	6		5					3		2			1
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

- GLO by L. Clason, 1836, Post Sta = 52+62.8
- N43W 45 12" Beech
- S60W 48 12" Hemlock
- Consumers Power Survey, 1965+-
- Set Pk nail per highway station
- NW 56.20 Hwy Marker
- SE 57.25 Hwy Marker
- NE 55.24 Steel Fence Post
- LCRC by R. Higgins, 1982, Pavement Box
- NW 58.20 Hwy Marker
- NE 55.24 Steel Fence Post
- SE 76.45 Set Spike in top center post guard rail
- SW 38.34 Set spike in top center post of guard rail

- Survey by N. Caldwell, 1980, No material
- Survey by T. Lapham, 1996, Found pavement box
- NW 58.20 Highway Marker
- NE 55.24 Steel Fence Post
- SE 76.45 Guard Rail Post
- SW 38.34 Guard Rail Post

MDOT Road Plans, No Material  
No corner set

Approved by Peer Review

12-16-99 DATE JLF INITIALS

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No GLO evidence found. Found 1/2" capped iron in monument box. Distances North and South match 1965 distances. No previous witnesses found.  
Accepted found iron as best available evidence of correct corner position.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"x36" rebar w/aluminum remon cap
- N46E 70.74 Utility Pole
- S15E 76.10 Guard Post
- S41W 39.83 Guard Post
- N60W 56.76 Tele Ped Post
- West 0.7 Centerline M-33



Recorded by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/23/1999