

Ogemaw County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

For corners in

Ogemaw  
 (County)

Located in:

Corner Code #

SECTION

1. Public Land Survey

T22N R02E  
 T22N R03E  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

M-9  
 A-9 ✓  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

2. Property Controlling  
 in Section

3. Miscellaneous  
 Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

 **3006801**  
 Page: 1 of 1  
 12/27/1999 09:09A  
 L-4 P-10  
 Manda Muzik, Ogemaw Co. Registrar SURC 9.00

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Timothy L. Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

Description of original monument and accessories and/or subsequent restoration:

GLO by L. Clason, 1838, Post  
 N26W 21 lks 20" Hemlock  
 S62W 31 lks 9" Hard Maple

N45E 78.59 Power Pole  
 S50W 78.19 Power Pole

LCRC by J. Nelson, 1988, Found 3/8" rerod in mon box  
 Az 49° 78.27 Power Pole  
 Az 153° 103.77 Michcon Aerial Mrk, 16" pipeline  
 Az 230° 78.58 Power Pole  
 Az 307° 113.19 Power Pole

Consumers Power Survey, 1965+, Found monument box  
 NE 76.18 Tele Pole  
 SE 73.35 Rd Marker  
 SW 82.34 Stub Pole  
 NW 113.5 Power Pole

LCRC by T. Lapham, 1993, Found 1/2" iron in mon box  
 N60W 113.10 Power Pole  
 N45E 78.59 Power Pole  
 S50W 78.19 Power Pole

Approved by Peer Review

12-16-99 DATE SJK INITIALS

Survey by N. Caldwell, 1973, No material

Survey by T. Lapham, 1997, Found iron  
 N60W 113.10 Power Pole

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No GLO evidence found. Found 3/4" iron in monument box at intersection centerlines of M-33 and M-55. Found 2 - 1965 witnesses, 3 - 1988 witnesses (2 witness distances appeared to be switched) and 3 - 1993 witnesses. Distances North and South 1 mile match 1965 survey. Accepted found iron as best available evidence of correct corner position.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod w/aluminum remon cap  
 N45E 78.59 Utility Pole  
 S30W 95.18 Horz Control Mark  
 S50W 78.19 Utility Pole  
 N60W 113.10 Utility Pole



Signed by Timothy L. Lapham  
 Surveyor's Michigan License No. 27595

Date 12/23/1999