

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 24 2000

SECTION

Ogemaw  
(County)

Located in:

Corner Code #

1. Public Land Survey

T22N R02E

M-11

T22N R3E

A-11

T R

T R

2. Property Controlling  
In Section

S

T R

S

T R

3. Miscellaneous  
Property In Sec.

S

T R

S

T R



3006795

Page: 1 of 1  
12/27/1999 09:09A  
L-4 P-4

Handa Muzik, Ogemaw Co. Registrar SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

M-11: GLO by L. Clason, 1838, Post  
Q-11 N12W 19 20' Hd Maple  
S15.5W 43 18" Hemlock

NW 77.45 Power Pole  
SW 67.50 Rd Sign Post

LCRC by T. Lapham, 1985, Found Pk nail  
East 40.65 Sq Cor Post  
N70W 77.70 Power Pole  
S70W 52.45 "T" in centerline conc headwall

LCRC by C. Lindgren, 1989, Found Pk nail  
Set 1/2" rerod w/cap stamped MDOT  
S85E 62.68 Wood Post  
S40E 96.70 Power Pole  
N45E 107.28 Power Pole  
N60W 77.54 Power Pole

Survey by D. Ledy, 1986, Found Pk nail  
Per recorded

Consumers Power Survey, 1965+-, Set Pk nail per MDOT sta

Approved by Peer Review

12-16-99  
DATE

SLP  
INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11: No evidence of GLO corner. Found 1/2" capped iron (MDOT) in monument box matching GLO call to stream North. Found 1 - 1965 witness, 1 - 1985 witness, and 3 - 1989 witnesses. Distances to M/A-9 and M/A-12 match 1965 survey, and distance to M/A-10 matches 1988 survey. Accepted found iron as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11: Set 5/8" rebar w/aluminum remon cap  
N-11 N45E 107.33 Utility Pole  
S45E 96.81 Utility Pole  
S70W 53.04 Top Cen of Culvert  
N65W 77.72 Utility Pole

Signed by [Signature]  
Surveyor's Michigan License No. 27595

Date 12/23/1999