

Ogemaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RF SURVEY & REGISTER

FEB 24 2000

For corners in

<u>Ogemaw</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22N R03E	E-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SECTION



3006800
Page: 1 of 1
12/27/1999 09:09A
L-4 P-9
Manda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-9: GLO by B.F. Hall, 1846, Post N62W 29 12" Beech S70E 8 18" Hemlock
Survey by R. Higgins, 1978, Fd Pk nail
S20E 77.8 Tele Pole
Survey by T Lapham, 1987, No mat'l
- LCRC by S. Barnett 1972, Fd Pk Nail
N44E 78.45 Power Pole
N38W 74.64 Power Pole
S43W 86.91 Power Pole
S20E 77.8 Tele Pole
Survey by D. Ledy, 1985, Fd Pk int centerline rds
N44E 78.45 Power Pole
N38W 74.64 Power Pole
S43W 86.91 Power Pole
S20E 77.80 Tele Pole
South 18.6 1/2" Bar
Survey by T. Lapham, 1996, Fd Iron
N44E 78.5 Power Pole
N38W 74.6 Power Pole
S43W 86.9 Power Pole
South 1.75 Center of M-55
- LCRC by N Caldwell, 1977, Fd Pk nail
N44E 78.45 Power Pole
N38W 74.64 Power Pole
S43W 86.91 Power Pole
S20E 77.80 Tele Pole
South 18.6 1/2" Bar
Survey by D. Ledy, 1985, Found Pk Int centerline rds
N44E 78.45 Power Pole
N38W 74.64 Power Pole
S43W 86.91 Power Pole
S20E 77.80 Tele Pole
South 18.6 1/2" Bar
Survey by T. Lapham, 1994, Fd capped iron
N44E 78.5 Power Pole
N38W 74.6 Power Pole
S43W 86.9 Power Pole
South 1.75 Center of M-55
- LCRC by N. Caldwell, 1978, Found 1/2" bar w/ cap
N44E 78.5 Power Pole
N38W 74.6 Power Pole
S43W 86.9 Power Pole
South 1.75 Center of M-55
Survey by T. Lapham, 1996, Fd Iron
N44E 78.5 Power Pole
N38W 74.6 Power Pole
S43W 86.9 Power Pole
South 1.75 Center of M-55
- Survey by N. Caldwell, 1980, No mat'l
Survey by T. Lapham, 1994, Fd 1/2" Iron in mon box
- Survey by R. Higgins, Pavement Box Iron 60' North and 33' East
Survey by T. Lapham, 1994, Fd 1/2" Iron in mon box
- Survey by L Cavanagh, 1975, Fd Pk nail
Iron 60' North and 33' East
Survey by J. Richardson, 1970, Set Pk Nail
N44E 78.45 Power Pole
N38W 74.64 Power Pole
S43W 86.91 Power Pole

Approved by Peer Review

12-16-99
DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-9: No evidence of GLO corner. Found 1/2" capped 1978 LCRC's. All surveys appear to use the same corner. Accepted found iron as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-9: Set 5/8" rerod w/ aluminum remon cap
S56E 90.31 Set spike in 10" J. Pine
S38W 86.45 Fd N&T in PP (OBT)
N48W 75.87 Fd N&T in PP (OBT)
N32E 78.46 FD N&T in Brace Pole (OBT)

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/23/1999

