

Ogemaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED BY &
RECEIVED

FEB 24 2000

SECTION

For corners in

Ogemaw
(County)

Located in:

Corner Code #

1. Public Land Survey

T22N R03E

E-11

T R

T R

T R

2. Property Controlling
In Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R



3006784

Page: 1 of 1
12/27/1999 09:09A
L-3 P-293

Wanda Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Timothy L Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

E-11: GLO by B.F. Hall, 1846, Post
N15E 30 10" Beech
S40E 18 5" Beech

S60W 62.27 Power Pole
S08W 91.22 Power Pole
N10E 83.68 18" Oak

S45E 42.57 Fence Post
North 38.28 Fence Cor
S25E 50.75 12" S. Pine

LCRC by S. Barnett, 1972, Found 1/2" rebar
S60W 62.27 Power Pole
S08W 91.22 Power Pole
N10E 83.68 18" Oak

Survey by N. Caldwell, 1976, Found 1/2" bar/cap
S60W 62.27 Power Pole
S08E 91.22 Power Pole
N12E 83.68 18" Oak

LCRC by N. Caldwell, 1977, Fd 1/2" bar & cap (r)
S60W 62.27 Power Pole
S08E 91.22 Power Pole
N12E 83.68 18" Oak

Survey by T. Lapham, 1994, Found 1/2" iron
S50W 62.24 Utility Pole
N60W 64.61 Utility Pole
S43E 27.42 15" Poplar
N52E 53.74 10" Poplar

Survey by S. Barnett, 1972, Found 1/2" rebar
S60W 62.27 Power Pole
S08W 91.22 Power Pole
N10E 83.68 18" Oak

Survey by T. Lapham, 1992, Found capped iron
S45E 42.57 Fence Post
North 38.28 Fence Cor
S25E 50.75 12" S. Pine

Survey by J. Richardson, 1970, Set 1/2"x24" bar

Survey by T. Lapham, 1996, Found capped iron

Approved by Peer Review

12-16-99
DATE


JLR
INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11: No GLO evidence found. Found 1/2" capped iron (27595) and all 4 - 1994 witnesses. Also found 2 - 1972 LCRC and 2 - 1977 LCRC witnesses. 1972 witnesses were for corner D-11 not E-11. Accepted found iron as best available evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11: Set 5/8" rebar w/ aluminum remon cap
West 6.0 Centerline Bedtelyon Road
N52E 53.74 12" Poplar
S43E 27.42 16" Poplar
S50W 62.24 Utility Pole
N60W 64.61 Utility Pole



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/23/1999