

**SURVEY &  
REMONUMENTATION**

JUN 02 1994

**OGEMAW COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED  
OGEMAW COUNTY, MI

LIBER 2 PAGE 233

93 DEC 29 PM 3:05

*Wanda Mizik*  
REGISTER OF DEEDS  
OGEMAW COUNTY

For corners in OGEMAW  
(County)

Located In: Corner Code #

1. Public Land Survey	T	22N	R	3E	M-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**TIMOTHY L. LAPHAM**, in a field survey on December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-3: 1838, CLASON, POST, WHITE PINE 24" S54W 10LKS; BEECH 10" N28W 28LKS; 1978+/-, COUNTY ROAD PLANS, CORNER MATERIAL, 3 WITNESSES; 1/27/1988, D. LEDY, LCRC 1-373, COR MAT, 3 WITS; 1992, T. LAPHAM, (132) NOT RECORDED, COR MAT, 3 WITS;

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-3: NO EVIDENCE OF GLO CORNER OR WITNESSES. SUBSEQUENT SURVEYS ALL USE THE SAME POINT. FOUND 1/2" X 18" REROD. ALL WITNESSES GONE DUE TO RECENT ROAD CONSTRUCTION. VERIFIED CORNER POSITION FROM PROPERTY CORNERS OF 1992 SURVEY. ACCEPTED FOUND CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER. THIS CORNER ESTABLISHED IN OGEMAW COUNTY REMONUMENTATION PROGRAM. SEE DOSSIER FOR DETAILED REPORT.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-3: SET 5/8" X 36" REROD WITH 3" OGEMAW COUNTY MONUMENT CAP  
AZ 270° 33.33' CI #27595  
AZ 230° 118.05' SPIKE IN SE FACE 7" BLACK CHERRY  
AZ 287° 107.51' SPIKE IN NORTH FACE 7" MAPLE  
AZ 42° 84.93' SPIKE IN SE FACE UTILITY POLE



Signed by *[Signature]*  
Surveyor's Michigan License No. 27595

Date 12/23/93