

MAY 28 1997

OGEMAW COUNTY REMONUMENTATION

LIBER 113 PAGE 94

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 4E	C - 13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

30 DEC 96 4:32 P.M.

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L. Lapham, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

GLO, L. Clason, 1838
Set post in swamp
W. Pine 15" N57W 15 links
Tam 8" S68E 9 links
Survey, Henning 8/21/41
Iron pipe and old post in center of old road grade
43.8 West to C1 T21N R4E
LCRC, Ledy 8/16/89 (Rec L2, P85-88)
Found 1-1/2" pipe
West 42.91' 1-1/2" pipe

ESE 45.54' Spike in 16" Willow
SSE 69.58' Spike in 20" Willow

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner found. Found 1-1/2" pipe and Ledy Wits. Pipe on fence line North in accord with Henning survey. Accepted found corner as best evidence of the position of the original corner,


APPROVED BY
PEER REVIEW

12-18-96 *TL*

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X 38" re-rod with 2-1/4" Aluminum cap Marked "1986 27595"
From Which:
N82E 35.77' 12" Ash
S85E 45.77' 26" Willow
S20E 69.51' 36" Willow
N88W 42.91' 5/8" Capped rerod C-1 T21N R4E



Signed by *Timothy L. Lapham*
Surveyor's Michigan License No. 27595

Date 12/27/96