

MAY 28 1997

OGEMAW COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 4E	E - 13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

30 DEC 96 4:32 P.M.

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Timothy L. Lapham, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO L. Clason 1838
Set post
S. Maple 15" N52E 43 links
W. Pine 14" N77W 12 links
1887, Lapham, Section break of Section 4 T21N R4E
Found rered at intersection of centerline roads

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

No evidence of GLO corner found. Found 1/2" iron in center line of road East-West at road North. Distances to F-13 and E-1 T21N R4E matches section break. Accepted found corner as best available evidence of the position of the original corner.

APPROVED BY
PEER REVIEW
12-18-96
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X38" re-rod with 2-1/4" Aluminum cap Marked "1996 27595"
From Which:
N38E 48.68' Fence post
S47W 33.78' Fence Corner Post
S70W 88.20' Fence Post
West 37.50' 5/8" capped rered E-1 T21N R4E



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/96