

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 4E	F - 13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L. Lapham, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO L. Clason, 1838
Set Post
B. Ash 12" N18E 45 links
Forked S. Maple 20" N11W 43 links
1987, Lapham, Section break of section 4 T21N R4E
Found 1/4"x1" steel bar by wood stake in
centerline road at fence north
No witnesses;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of GLO corner found. Found pry bar at fence north. Distances East and West match 1987 section break. Accepted found bar as best available evidence of the position of the original corner.

APPROVED BY
PEER REVIEW
12-18-96 JL
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X3/8" re-rod with 2-1/4" Aluminum cap Marked "1996 27595"
From Which:
North 31.22' Fence Corner Post
S51W 53.49' 1/2" capped iron
S79W 115.82' 8" Ash
N50W 88.00' Utility Pole
West 41.74' 5/8" capped iron F-1 T21N R4E



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/96

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												