

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>23</u> N. R. <u>1</u> E.	C-13
2. PROPERTY CONTROL- ING IN SECTION.....	T. <u>23</u> N. R. <u>1</u> E.	15; 16
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. E. S. R. W.	
4. LOT NO.	RECORDED PLAT.....	
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, KENNETH J. OSTLING, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on OCTOBER 25, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX
 C. CONTINUED

16
 SET 5/8" IRON BAR W/ CAP
 9" RED OAK N2°W 5.9'
 7" BLACK OAK N56°E 29.0'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 15 SET BY STANDARD SURVEY PROCEDURE FOR THE SUBDIVISION OF SECTIONS.
- C-13 RESTORED CORNER BY PROPORTIONATE MEASUREMENT BETWEEN THE SW OF 31 AND SE OF 32, AT THE LATITUDE OF E-W FENCE LINE. FALL NEAR CENTERLINE OF FIRE-LINE NORTH. COULD NOT IDENTIFY ANYTHING FOR U.S. EVIDENCE OR A PREVIOUS CORNER.
- 16 SET CORNER BY STANDARD SURVEY PROCEDURE FOR THE SUBDIVISION OF SECTIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;"><u>15</u></p> <p>SET 5/8" ROD W/CAP 4" WHITE PINE N36°E 32.3' 16" WHITE OAK N46°W 76.5'</p>	<p style="text-align: center;"><u>C-13</u></p> <p>SET DNR MONUMENT, BELOW SURFACE 14" RED OAK N26°W 38.5' 12" RED OAK N24°E 46.1'</p>
--	---

SIGNED BY Kenneth J. Ostling
 KENNETH J. OSTLING
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 1/18/83



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ OGEMAW COUNTY