

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>23</u> N. ●, R. <u>1</u> E. ●	K-8
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	, T. <u>23</u> N. ●, R. <u>1</u> E. ●	14, 16
3. MISCELLANEOUS PROPERTY IN SECTION <u>23</u>	, T. <u>23</u> N. ●, R. <u>1</u> E. ●	K-8/14
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 6, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 6, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- K-8 Set corner by single proportionate measurement between section corners. Stump of possible U.S. corner tree is about 2' south, with what appears to be an old face.
  - 14 Set by standard survey procedure for the subdivision of sections.
  - 16 Set by standard survey procedure for the subdivision of sections.
  - K-8/14 Set by standard survey procedure for the subdivision of sections.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	K-8	14	16
Set DNR mon. & red-top post	5/8" x 36" Iron Bar	5/8" x 36" Iron Bar	
6" R. Oak N11°W 14.0	4" R. Oak S85°E 6.65	5" W. Pine S50°W 30.2	
4" W. Oak N42°E 7.5	6" W. Oak N30°E 34.7	5" W. Pine S72°E 20.0	
30" W. Pine Stump S20°E 2.5			
	K-8/14		
	5/8" x 36" Iron Bar		
	4" W. Oak N20°E 4.6		
	6" W. Oak S50°E 11.0		

SIGNED BY Kenneth J. Ostling DATE 12-15-76  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ OGEMAW COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET