

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Ogemaw Located In _____ Corner Code # _____
 (County)

1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S <u>2</u>	T <u>23N</u>	R <u>1E</u> <u>6</u>
	S <u>2</u>	T <u>23N</u>	R <u>1E</u> <u>9</u>

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on October 28, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2	●	●	1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| 6- George Henning RLS #2240 set corner c. 1944 prior to doing the "Supervisor's Plat of Second Addition to Horseshoe Lake Resort". | 9- George Henning RLS #2240 set 1 1/4" X 6' iron pipe c. 1944 while surveying in the area. |
|--|--|

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

- | | |
|--|---|
| 6- Found a 1" pipe in concrete fitting "Supervisors Plat of Second Addition to Horseshoe Lake Resort." | 9- Found a 1" pipe fitting George Henning RLS #2240 c. 1944 survey. |
|--|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-----------------------------|---------------------------------|
| 6- 1" iron pipe in concrete | 9- 1" iron pipe |
| Wit: 11" Oak N07°W 17.31' | Wit: 12" Twin Oak S34°W 33.27' |
| 20" Oak S57°E 36.73' | 9" Oak S56°W 23.52' |
| 24" Oak S09°W 55.94' | 12" & 18" Twin Oak N65°W 26.47' |
| 9" Maple S74°W 57.64' | 14" Maple N46°W 38.80' |
| Carsonite post North 1' | Carsonite post North 1' |

Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-21-99

