

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*Ostling*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>23</u> N. <u>•</u> , R. <u>2</u> E. <u>•</u>	<u>E-6; F-6</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>23</u> N. <u>•</u> , R. <u>2</u> E. <u>•</u>	<u>3; 4</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 29, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-6 Set corner in average centerline of N-S road, in line with fence east. This point best fits fences and occupation in two miles. Best available evidence.
- F-6 Set corner at intersection of true 1/4 lines, per standard procedure.
- 3 Set by standard survey procedure for subdivision of sections.
- 4 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>E-6 Set DNR Mon. below Surf. 4" Maple N89°E 27.0' 5" W. Oak N35°E 49.3'</p>	<p>F-6 Set 2-1/2' of 1" Pipe 8" W. Oak N76°W 29.9' 11" R. Oak N05°W 13.4'</p>	<p>3 Set 2-1/2' of 1" Pipe, 1/2" Re-Rod Inside 8" B. Oak S65°W 52.9' Face of Tw. 5" Oaks S57°E 16.25' No Mark 4" R. Pine S33°E 28.8'</p>
<p>4 Set 2-1/2' of 1" Pipe 8" B. Oak N68°E 9.9' 6" B. Oak S15°E 6.1'</p>		

SIGNED BY *Kenneth J. Ostling*  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 8/1/80



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_