

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Monument

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>23</u> N. <u>2</u> E.	<u>E-7; F-7</u>
2. PROPERTY CONTROLLING IN SECTION	<u>16</u> , T. <u>23</u> N. <u>2</u> E.	<u>15; 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S. <u>2</u> E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 29, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-7 Set corner from possible OBT stump, which places corner in center of N-S road, and compatible with fence occupation for one mile north and south. Best available evidence.
- F-7 Set corner by proportionate measure between section corners. Could not positively identify original evidence.
- 15 Set by standard survey procedure for the subdivision of sections.
- 16 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7	F-7
Set DNR Mon.	Set DNR Mon.
6" W. Pine S30°E 67.1'	7" Maple S07°E 11.4'
11" W. Pine N88°E 38.3'	6" R. Oak N70°W 13.6'
15	16
Set 2-1/2' of 1" Pipe	Set 1" x 24" Pipe
7" W. Oak N87°E 8.9'	5" J. Pine S65°E 24.5'
8" R. Oak S12°W 8.8'	6" J. Pine S15°W 10.4'

SIGNED BY Kenneth J. Ostling DATE 8/30
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)