

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 23 N. R. 2 E.	C-1; C-3
2. PROPERTY CONTROLLING IN SECTION 6	T. 23 N. R. 2 E.	14
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 12, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-1 Set this corner at U.S. record measurement (14.5') West of 1/2" bar believed to be the SE corner of Sec 31, which was previously used in surveys by Henning and Richard Miller Oscoda.

14 & C-3 Set by standard survey procedure for the subdivision of sections, at 653.48 North of SE corner.

~~14~~ **14** Corner set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 14 & C-3	14 & C-3 C-1	14
Set 5/8 rod w/RLS cap	Set 1' of 5/8" rod w/RLS cap	Set 5/8" Rod w/RLS Cap
3" R. Pine S53°E 30.8'	Power Pole N11°W 33.3'	8" Oak S77°W 81.3'
4" R. Pine N30°E 32.3'	10" R. Pine S42°W 108.5'	5" R. Pine N13°E 72.8'
	Nail & Tag	

SIGNED BY Kenneth Ostling

DATE 9/4/80


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

Ogemaw
Assessor