

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 23 N. R. 2 E.	A-1; B-1; <del>12</del>
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	T. 23 N. R. 2 E.	12, B-3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 12, \_\_\_\_\_, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-1 Found 1 1/2" iron bar in road intersection, used in surveys in adjoining sections.
- 3-1 Set corner by proportionate measurement between section corners.
- 3-3-12 Set corner by standard survey procedure for the subdivision of sections, 656.57 North of S 1/4 corner.
- 12 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	A-1	B-1	12 - B-3
	Left 1/2" iron bar in place	Set 1' of 5/8" rod w/RLS cap	Set 5/8" Rod w/RLS Cap
*	7" J. Pine S38°W 43.9'	6" J. Pine S13°E 46.2'	3" W. Pine N81°W 6.5'
*	12" Oak S23°E 41.6'	8" J. Pine S30°W 46.5'	3" w. Pine N01°W 16.6'
		S 1/4 Sec 31, T24-2E S89°33'00"E 24.1'	
* Nail & Tag			12
			Set 5/8" Rod w/RLS Cap
			6" J. Pine N29°W 10.3'
			6" J. Pine S41°W 16.0'

SIGNED BY Kenneth Ostling DATE 9/2/80

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


FOR STATE AND UNITED STATES AGENCIES: \_\_\_\_\_

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

Ogemaw

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET