

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ogemaw

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>23NR</u>	<u>2E</u>	<u>B-1</u>
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property Controlling in Section	S	_____	T	R
	S	_____	T	R
3. Miscellaneous Property in Sec.	S	_____	T	R
	S	_____	T	R

LIBER. **3** PAGE **26**

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

28 DEC 95 3:21 P.M.

WANDA MUJIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Timothy L. Lapham, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1: GLO Not Set;
LCRC Ostling 9/4/80 (Rec 1-221, 11/18/80), Set 5/8"X12" Rod by SPM, 3 Wits;


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1: Found 5/8" capped iron at SPM between Township Corner and C-1 T23N R2E Accepted found corner as correctly established corner within acceptable limits. See dossier for additional information

APPROVED BY
PEER REVIEW
12/11/95 *[Signature]*
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1: Set 5/8"X36" Rerod with 3-1/4" Aluminum Ogemaw Remon Cap Marked "27595 1995"
N48E 73.13' 12" Jack Pine w/spike
East 14.53' 3/4" Capped Pipe (B-13 T24N R2E)
S43E 56.40' 6" Jack Pine w/spike
S11E 46.48' 10" Jack Pine w/spike and 2 Face Blazes
S02W 33.45' DNR Post w/spike
S27W 46.84' 10" Jack Pine w/spike and 2 Face Blazes
N09W 40.24' 10" Jack Pine w/spike



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12-28-95