

SURVEY & REMONUMENTATION

APR 29 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **OGEMAW** (County) **COMMISSION**

LIBER 3 PAGE 28

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

28 DEC 95 3:22 P.M.

MANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Located In:	Corner Code #
1. Public Land Survey T <u>23NR 2E</u>	<u>D-1</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling S _____ T _____ R _____	_____
In Section S _____ T _____ R _____	_____
3. Miscellaneous S _____ T _____ R _____	_____
Property in Sec. S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Timothy L. Lapham, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1: GLO Not set;
LCRC Lapham 2/2/89 (Rec 2-41, 3/22/89), Set 3/4"X24" Pipe, 5 Wits;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1: Found capped pipe in accord with record LCRC 2-41. Corner is at SPM on Township line within acceptable tolerances. Accepted found corner as best evidence of properly positioned corner. See dossier for additional information.

APPROVED BY
PEER REVIEW
12/11/95 JM
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1: Set 5/8"X36" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1995"
From Which:
North 1.0' Centerline Pavement.
N11E 62.04' 12" Jack Pine
East 23.44' 5/8" Remon Monument
East 63' Trail North-South
S63E 59.01' 12" Red Pine
S08W 51.45' 12" Jack Pine w/spike

Signed by [Signature]

Date 12/28/95

Surveyor's Michigan License No. 27595

