

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ogemaw

(County)

Located In:

Corner Code #/

1. Public Land Survey	T	23NR	2E	E-1
	T		R	
	T		R	
	T		R	
2. Property Controlling In Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

LIBER 3 PAGE 29

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

28 DEC 95 3:22 P.M.

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Timothy L. Lapham, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: GLO Mullett 1846, Set Post, 10" Spr. Pine S19W 33lnks, 12" Spr. Pine S32E 11lnks; LCRC Lapham 2/2/89(Rec 2-41), Set 3/4"X24" Pipe, 4 Wits

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1: Found capped pipe at GLO distance from standard corner in accord with record LCRC 2-41. Accepted found corner as best evidence of properly established accepted corner. See dossier for additional information.

APPROVED BY
PEER REVIEW
12/11/95
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1: Set 5/8"X36" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1995"
From Which:
North 0.3' Centerline Pavement
N10E 52.17' Power Pole
East 12.52' 5/8" Remon Monument
S38E 57.09' 8" Jack Pine
S32W 68.93' 10" Oak

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/28/95

