

**SURVEY &  
REMONUMENTATION**

APR 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 3 PAGE 30

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

28 DEC 95 3:22 P.M.

WANDA NUZIK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

For corners in Ogemaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 23NR 2E	F-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Timothy L. Lapham, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
F-1: GLO Not Set  
LCRC Lapham 2/2/89(Rec 2-41), Set 3/4"X24" Pipe by SPM, 4 Wits;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
F-1: Found 3/4" capped Pipe in accord with recorded LCRC. Accepted found corner as being correctly established at SPM and on Township line within allowable tolerances. See dossier for additional information.

APPROVED BY  
PEER REVIEW  
12/11/95 ja  
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
F-1: Set 5/8"X36" rerod with 3-1/4" Aluminum Ogemaw Remon Cap marked "27595 1995"  
From Which:  
North 2' Centerline Fire Lane  
S60E 33.58' 12" Oak  
S07W 63.01' 6" Jack Pine  
S64W 42.69' 6" Red Pine  
West 7.64 5/8" Capped Iron  
N22W 19.91' 10" Oak



Signed by [Signature] Date 12/28/95  
Surveyor's Michigan License No. 27595