

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 113 PAGE 33

STATE OF MICHIGAN
 OGEHAW COUNTY
 RECORDED

28 DEC 95 3:23 P.M.

WANDA MUZIK
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

For corners in
Ogemaw
 (County)

Located In: Corner Code #

1. Public Land Survey T 23N R 2E J-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Timothy L. Lapham, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1: GLO Not Set;
 LCRC Lapham 2/2/89 (Rec 2-67, 3/22/89), Set Capped Pipe by SPM, 5 Wits;
 Survey Lapham 12/23/92 (Rec 5-344), Reference LCRC 2-67;
 Survey Lapham 7/6/94 (Rec 5-461), Reference LCRC 2-67;
 Consumers Power Co. Survey 1967-8 Dorcey, Did not establish this corner.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1: Found capped iron in accord with recorded LCRC and Surveys. Within acceptable tolerances of being SPM. Accepted found corner as best evidence of properly established corner. See dossier for additional information.

APPROVED BY
 PEER REVIEW
 12/20/95 *jm*
 DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1: Set 5/8" rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1995"
 From Which:
 N61E 75.02' Fence Post w/nail
 East 59.77' 5/8" Remon Monument
 S50E 81.02' Post
 South 1.0' Centerline Pavement
 S20W 64.40' Power Pole
 N30W 57.04' Power Pole w/nail



Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/28/95