

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 113 PAGE 35

For corners in
Ogemaw

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	23NR	2E	L-1
	T		R	
	T		R	
	T		R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

28 DEC 95 3:23 P.M.

WANDA MUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L. Lapham, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-1: Not Set By GLO
Survey Caldwell 4/2/75 (Rec 2-11, 10/3/75), No Cor Mat, No Wits;
Survey Caldwell 11/15/76 (Rec 2-288, 6/17/77), No Cor Mat, No Wits;
Survey Caldwell 11/20/80 (Rec 3-271, 1/26/91), No Cor Mat, No Wits;
LCRC Lapham 1/23/89 (Rec 2-52, 3/22/89), Fd LLS Capped Iron, 4 Wits;
Unrecorded Survey By Lapham
Survey Consumers Power CO. No Date, Found 3/8" Iron rod in line with fence south, No Wits


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-1: Found 1/2" iron bar in agreement with with previous surveys. Corner is 0.12' South of Township line and 5.08' West of SPM position. Because there is no GLO evidence for corners either East or West and a corner exists which is on the fence South and is at half the record offset for K-1 from K-13 T24N, R2E, I accepted the found corner as best evidence of accepted corner position. See dossier for additional information.

APPROVED BY
PEER REVIEW
12/20/95 *[Signature]*
DATE P.A. 345 of 1990

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-1: Set 5/8" X 3/16" Rerod with 3-1/4" Aluminum Ogemaw Remon cap marked "27595 1995"
From Which:
North 0.8' Centerline Pavement
N56E 61.75' 160.41' Tag in 8" Red Pine
East 9.45 5/8" Ogemaw Remon Monument
South 54.66 12" Elm
S61W 63.75' 4X4 Pipeline Marker



Signed by *[Signature]*
Surveyor's Michigan License No. 27595

Date 12/28/95