

Ogemaw County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

FEB 24 2000

For corners in

Ogemaw
(County)

Located in:

Corner Code #

SECTION

1. Public Land Survey

T22N R02E M-1
T22N R03E A-1
T23N R02E M-13
T23N R03E A-13

2. Property Controlling
In Section

S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___



3006791
Page: 1 of 1
12/27/1999 09:09A
L-3 P-300

Handa Muzik, Ogemaw Co. Register SURC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Timothy L. Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO by L. Gieson, 1838, Post
S46W 40 ft 12" Hemlock
N37E 43 ft 16" W. Birch

Survey by N. Caldwell, 1979, No Material

Survey by R. Higgins, 1979, Iron in prvnt box

Survey by R. Higgins, 1978, No material
(shown in centerline road)

MDOT Plans, No material, corner is P.I.

Consumers Power Survey, 1965+-, Found boat spike
SW 58.0 Tele Pole
NE 37.0 Rd Sign Post

Approved by Peer Review


12-16-99 DATE  INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No GLO evidence found. Found iron in monument box at P.I. of road per MDOT. Corner appears to be same used by all surveys since GLO. Accepted found iron as best evidence of correct corner position.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" rerod w/ aluminum remon cap
N34E 120.67 Utility Pole
S85E 103.91 NW Cor Block Bldg
S35W 96.45 Utility Pole
N25W 110.91 Utility Pole
West 1.0 Centerline M-33

Signed by 
Surveyor's Michigan License No. 27595

Date 12/23/1999