

Ogemaw County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 FEB 24 2000

For corners in

SECTION

Ogemaw Located In: Corner Code #
 (County)

1. Public Land Survey T22N R02E M-1
 T22N R03E A-1
 T23N R02E M-13
 T23N R03E A-13 ✓

2. Property Controlling S T R
 In Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

3006791
 Page: 1 of 1
 12/27/1999 09:09A
 L-3 P-300
 Henda Muzik, Ogemaw Co. Register SURC 9.00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Timothy L. Lapham, in a field survey on December, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- GLO by L. Clason, 1838, Post
- S46W 40 1/2 12" Hemlock
- N37E 43 1/2 16" W. Birch
- Survey by N. Caldwell, 1979, No Material
- Survey by R. Higgins, 1979, Iron in pvmt box
- Survey by R. Higgins, 1978, No material (shown in centerline road)
- MDOT Plans, No material, corner is P.I.
- Consumers Power Survey, 1985+, Found boat spike
- SW 58.0 Tele Pole
- NE 37.6 Rd Sign Post

Approved by Peer Review
12-16-99 JLR
 DATE INITIALS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No GLO evidence found. Found iron in monument box at P.I. of road per MDOT. Corner appears to be same used by all surveys since GLO. Accepted found iron as best evidence of correct corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8"x36" rod w/ aluminum remon cap
- N34E 120.67 Utility Pole
- S65E 103.91 NW Cor Block Bldg
- S35W 98.45 Utility Pole
- N25W 110.91 Utility Pole
- West 1.0 Centerline M-33

Signed by [Signature]
 Surveyor's Michigan License No. 27595

Date 12/23/1999