

SURVEY & REMONUMENTATION

MAY 0 8 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OGEMAW

COMMISSION

LIBER

2 PAGE 254

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

3 JAN 95 9:33 A.M.

WANDA NUZIK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

(County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>23N</u> R <u>3E</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	10	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-1: NOT SET BY GLO
CALDWELL 1-7 AUG 1971, NO CORNER MATERIAL, NO WITS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-1: NO EVIDENCE FOUND OF ESTABLISHED POSITION
SET CORNER MIDWAY BETWEEN RECORDED CORNERS C1 AND E1 ON TOWNSHIP LINE, 6.78' EAST OF RECORDED CORNER D-13 T24N R3E
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE CORRECT POSITION OF THE ORIGINAL CORNER

CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY
PEER REVIEW

12-21-94 *TL*

DATE _____ P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-1: SET 5/8"x36" ROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX
N39E 46.43' NAIL IN POWER POLE
S30E 76.44' NAIL IN 16" W. PINE
S49W 60.40' 1/2" IRON BAR
WEST 6.76' REMON MONUMENT
N29W 64.96' NAIL IN 6" ASPEN

Signed by *Timothy L. Lapham*

Date 12/29/94

Surveyor's Michigan License No. 27595