

# SURVEY & REMONUMENTATION

MAY 0 8 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OGEMAW

(County)

Located In:

Corner Code #

- |                                       |   |                |       |
|---------------------------------------|---|----------------|-------|
| 1. Public Land Survey                 | T | <u>23NR 3E</u> | E-1   |
|                                       | T | R              | _____ |
|                                       | T | R              | _____ |
|                                       | T | R              | _____ |
|                                       | T | R              | _____ |
| 2. Property Controlling<br>in Section | S | T              | R     |
|                                       | S | T              | R     |
| 3. Miscellaneous<br>Property in Sec.  | S | T              | R     |
|                                       | S | T              | R     |

LIBER 2 PAGE 255  
STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

3 JAN 95 9:33 A.M.

WANDA MUZIK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Timothy L. Lapham, in a field survey on December, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
E-1: GLO CLASON 1846, SET POST,  
BEECH 24" S39W 35L.,  
BEECH 8" S55E 22L.  
KING LCRC 2-121, FEB 1991, FD IRON 3 WITS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
E-1: FOUND UNLEGIBLE CAPPED IRON

FOUND RECORDED WITNESSES:

S42E 46.44 SPIKE IN POWER POLE

S06E 27.92' SPIKE IN POWER POLE

N58W 64.46 SPIKE IN 30" MAPLE (RECORDED AS 30" WILLOW)

ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER,

CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994

SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY  
PEER REVIEW

12-21-94 TL

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
E-1: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX

N42E 37.04' 1/2" IRON BAR


S41E 46.44' SPIKE IN POWER POLE

S06E 27.92' SPIKE IN POWER POLE

N58W 64.46' SPIKE IN 30" MAPLE

WEST 9.90' REMON MONUMENT, E-13 T24N R3E

Signed by



Date

12/29/94

Surveyor's Michigan License No.

27595