

**SURVEY &  
REMONUMENTATION**

MAY 03 1995

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
OGEMAW

(County)

Located In:

Corner Code #

- |                                    |   |             |           |                |
|------------------------------------|---|-------------|-----------|----------------|
| 1. Public Land Survey              | T | <u>23NR</u> | <u>3E</u> | <u>G-1</u>     |
|                                    | T | _____       | R _____   | _____          |
|                                    | T | _____       | R _____   | _____          |
|                                    | T | _____       | R _____   | <u>Seg. #1</u> |
| 2. Property Controlling in Section | S | _____       | T _____   | R _____        |
|                                    | S | _____       | T _____   | R _____        |
| 3. Miscellaneous Property in Sec.  | S | _____       | T _____   | R _____        |
|                                    | S | _____       | T _____   | R _____        |

LIBER

2 PAGE 256

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

3 JAN 95 9:33 A.M.

WANDA MUZIK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- G-1: GLO CLASON 1846, SET POST  
CEDAR 10" S60E 34 LKS  
FIR 4" S22W 31 LKS  
CADWELL SURVEY 1-540 DEC 1974, NO CORNER MAT, NO WITS  
KING LCRC 2-113 FEB 1991, FD IRON, 4 WITS

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- G-1: FOUND 1/2" IRON  
FOUND RECORDED WITNESSES:  
N75E 131.97' SPIKE IN POWER POLE  
S02E 31.27' SPIKE IN POWER POLE  
ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION,  
CORNER APPROVED AT PEER REVIEW MEETING HELD DECEMBER 21, 1994  
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY PEER REVIEW	
<u>12-21-94</u>	<u>TL</u>
DATE	P.A. 345 of 1990

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- G-1: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX  
N76E 131.97 SPIKE IN POWER POLE  
S29E 84.38' SET SPIKE IN 8" SPRUCE  
S02E 31.27 SPIKE IN POWER POLE  
N26W 103.08' SET SPIKE IN 8" CEDAR

Signed by *Timothy L. Lapham*

Date 12/29/94

Surveyor's Michigan License No. 27595