

**SURVEY &
REMONUMENTATION**

MAY 03 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
OGEMAW
(County)

Located In:	Corner Code #
T <u>23N</u> R <u>3E</u>	<u>H-1</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	<u>Seg. #1</u>
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

LIBER 2 PAGE 257
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED
3 JAN 95 9:34 A.M.
WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-1: GLO CLASON 1846, SET POST

- SPRUCE 10" N22E 22LKS
- CEDAR 8" N18W 6LKS
- CALDWELL SURVEY 1-540 DEC 1974, NO CORNER MAT, NO WITS
- KING SURVEY 5-162 APRIL 1992, NO CORNER MAT NO WITS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-1: FOUND UNLEGIBLE CAPPED 1/2" IRON

HISTORICALLY RECORDED AS A COMMON CORNER TO H13 T24N R3E
THEORITICAL POSITION 1.24' WEST
EXISTTING CORNER WITHIN ALLOWABLE ERROR LIMITS FOR CORNER, ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE CORRECT CORNER POSITION

CORNER APPROVED AT PEER REVIEW MEETING HELD December 21, 1994
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY
PEER REVIEW

12-21-94 TL

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-1: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX

- N23E 69.15' SET SPIKE IN 8" CEDAR
- S21E 88.04' SET SPIKE IN 8" SUGAR MAPLE
- S47W 87.40' SET SPIKE IN 8" SPRUCE
- N32W 74.74' SET SPIKE IN 6" ASPEN

Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/27/94