

SURVEY & REMONUMENTATION

MAY 03 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OGEMAW

(County)

Located In:

Corner Code ##

- | | | | |
|---------------------------------------|-------------------------|---------------|-------|
| 1. Public Land Survey | T <u>23NR</u> <u>3E</u> | <u>I-1</u> | |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | <u>Seg. 1</u> | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |

LIBER

2 PAGE 258

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

3 JAN 95 9:34 A.M.

WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-1: GLO CLASON 1846, SET POST

- CEDAR 8" N44E 29LKS
- CEDAR 9" N58W 7 LKS
- SPRUCE 10" S38W 53LKS
- CEDAR 8" S13E 37LKS

1945 SHADKO(DNR), ESTABLISHED CORNER BASED ON FENCE SOUTH

*** NOTE: CORNER COMMON TO I-13 T24N R3E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-1: FOUND 1/2" IRON

DISTANCE EAST & WEST AGREE WITH GLO
REMNENT OF OLD PAGE WIRE FENCE SOUTH ON CORNER
ACCEPTED FOUND IRON AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

CORNER APPROVED AT PEER REVIEW MEETING HELD DECEMBER 21, 1994
SEE DOSSIER FOR ADDITIONAL INFORMATION

**APPROVED BY
PEER REVIEW**

TL

DATE 12-21-94 P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-1: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX

- N59E 81.20' FD NAIL IN 10" TAMARACK
- S23E 50.05' FD NAIL IN 10" TAMARACK
- S70W 88.54' FD NAIL IN POWER POLE
- N15W 74.86 FD NAIL IN 10" TAMARACK

Signed by _____

Timothy L. Lapham

Date 12/29/94

Surveyor's Michigan License No. 27595