

SURVEY & REMONUMENTATION

MAY 0 8 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OGEMAW <small>(County)</small>	Located in:	Corner Code ##
1. Public Land Survey	T <u>23N</u> R <u>3E</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **2** PAGE **250**

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

3 JAN 95 9:32 A.M.

WANDA MUZIK
Register of Deeds Stamp & File Number
REGISTER OF DEEDS

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-1: NOT SET BY GLO

CALDWELL SURVEY 1-428 APRIL 1974, NO CORNER MATERIAL, NO WITS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-1: NO EVIDENCE FOUND OF EXISTING CORNER

CORNER SET MIDWAY BETWEEN RECORDED CORNERS K-1 AND M-1 ON TOWNSHIP LINE 5.52' EAST OF EXISTING CORNER L13 T24N R3E
ACCEPTED ESTABLISHED CORNER AS BEST AVAILABLE EVIDENCE OF THE CORRECT POSITION OF THE ORIGINAL CORNER.
CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY
PEER REVIEW

12-21-94 *TL*

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-1: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX

NORTH 1.6' CENTERLINE ROSE CITY ROAD
N73E 7.15' 3/8" IRON BAR
S03W 49.74 CONCRETE MONUMENT
S56W 50.30 TRIPLE BLACK WALNUT
WEST 5.52' REMON MONUMENT L13 T24N R3E
N04W 50.32' CONCRETE MONUMENT
N03W 49.74' CONCRETE MONUMENT

STATE OF MICHIGAN
TIMOTHY L. LAPHAM
PROFESSIONAL SURVEYOR
NO. 27595

Signed by

Date

12/29/94

Surveyor's Michigan License No. 27595