

# SURVEY & REMONUMENTATION

MAY 0 8 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OGEMAW

(County)

COMMISSION

Located In:

Corner Code #

- |                                    |                          |     |                |
|------------------------------------|--------------------------|-----|----------------|
| 1. Public Land Survey              | T <u>23N</u> R <u>3E</u> | M-1 |                |
|                                    | T _____ R _____          |     |                |
|                                    | T _____ R _____          |     |                |
|                                    | T _____ R _____          |     | <i>Leg. #1</i> |
| 2. Property Controlling in Section | S _____ T _____ R _____  |     |                |
|                                    | S _____ T _____ R _____  |     |                |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  |     |                |
|                                    | S _____ T _____ R _____  |     |                |

LIBER

2

PAGE 261

STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED

3 JAN 95 9:35 A.M.

WANDA MUZIK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-1: CLASON 1938, SET POST, B. OAK 18" N66E 34L., S. MAPLE 14" S42W 39L., CALDWELL 4/8/1974, SURVEY 1-428, NO CORNER MATERIAL OR WITNESSES  
 CALDWELL 6/26/1974, SURVEY 1-440, NO CORNER MATERIAL OR WITNESSES  
 CALDWELL 9/8/1975, SURVEY 2-31, NO CORNER MATERIAL OR WITNESSES  
 CALDWELL 10/21/1976, SURVEY 2-197, NO CORNER MATERIAL OR WITNESSES  
 HIGGINS 8/02/1982, SURVEY 3-380\*2, NO CORNER MATERIAL FOUND BAR AT 33' NORTH SET BAR AT 50' NORTH

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- M-1: FOUND CAPPED IRON # NOT LEGIBLE, IN CENTERLINE OF ROAD E-W, DISTANCE EAST MATCHES PREVIOUS, DISTANCE WEST 1.6' SHORT OF PREVIOUS, CAPPED IRON NORTH BENT TO NORTH APPARENT DURING ROAD RECONSTRUCTION MEASURES 51.32' TO TOP OF IRON AS IS, ENTIRE R/W IRON APPEARS TO BE LEANING, ACCEPTED FOUND IRON AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION, CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994. SEE DOSSIER FOR ADDITIONAL INFORMATION.

APPROVED BY  
PEER REVIEW

*12-21-94*      *TL*

DATE                      P.A. 345 of 1990

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- M-1: SET 5/8"x36" REBAR WITH 3-1/4" ALUMINUM REMON CAP IN MON BOX  
 S02W 42.39 SET SPIKE IN POWER POLE  
 S32W 54.75 SET SPIKE IN 6" BALSAM FIR  
 N56W 76.39 SET SPIKE IN 10" OAK  
 N34E 48.85 SET SPIKE IN 8" OAK

Signed by

Date

12/29/94

Surveyor's Michigan License No. 27595