

# SURVEY & REMONUMENTATION

MAY 03 1995 LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
OGEMAW

COMMISSION

	Located in:	Corner Code #:	
(County)			
1. Public Land Survey	T <u>23N</u> R <u>3E</u>	<u>M-2</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	<u>Seg. 1</u>	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

LIBER **2** PAGE **262**  
STATE OF MICHIGAN  
OGEMAW COUNTY  
RECORDED  
3 JAN 95 9:35 A.M.

WANDA MUZIK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, Timothy L. Lapham, in a field survey on December, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
M-2: GLO CLASON 1838, SET POST  
W. PINE 22" S31W 26LKS  
Y. PINE 14" N47W 71LKS  
CALDWELL SURVEY 1-13 JULY 1971, NO COR MAT, NO WITS

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11							
5												
6	16	17	16	15	14	1						
7												
8	19	20	21	22	23	2						
9												
10	30	29	28	27	26	2						
11												
12	31	32	33	34	35	3						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M-2: FOUND UNLEGIBLE CAPPED IRON  
DISTANCE NORTH AND SOUTH AGREE WITH GLO  
ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER  
  
CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994  
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY  
PEER REVIEW

12-21-94 *JL*

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-2: SET 5/8" x 36" REBOD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP  
N64E 30.45' NAIL IN TRIPLE 10" PIN OAK  
S05W 9.43' NAIL IN TWIN 8" OAK  
N65W 25.81' NAIL IN 10" PIN OAK  
N08W 47.89' NAIL IN 12" PIN OAK

Signed by *Timothy L. Lapham* Date 12/29/94  
Surveyor's Michigan License No. 27595