

**SURVEY &
REMONUMENTATION**

MAY 03 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>OGEMAW</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23NR</u> <u>3E</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	<u>Seg. #1</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LISE 2 PAGE 264
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED
3 JAN 95 9:36 A.M.
WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23	2					
9											
10	30	29	28	27	26	2					
11											
12	31	32	33	34	35	3					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-4: GLO CLASON 1838, SET POST
Y. PINE 20" S36W 30LKS
HEMLOCK 10" N80W 34LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-4: NO EVIDENCE OF GLO CORNER FOUND
SET CORNER MIDWAY ON LINE BETWEEN ESTABLISHED CORNERS M-3 AND M-4
CORNER POSITION AGREES WITH GLO CALL TO FALL ON NARROW RIDGE IN SWAMP
ACCEPTED ESTABLISHED CORNER AS BEST AVAILABLE EVIDENCE AS TO THE CORRECT POSITION OF THE ORIGINAL CORNER
CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY
PEER REVIEW
12-21-94 TL
DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-4: SET A 5/8"x36" REROD WITH ALUMINUM OGEMAW REMON CAP
S59W 35.84 SET SPIKE IN 4" BALSAM FIR
N14W 5.17 SET SPIKE IN 6" RED PINE
N39E 9.61 SET SPIKE IN 8" SPRUCE
S75E 48.51 SET SPIKE IN 10" WHITE OAK
NORTH 17+/- WATERS EDGE
SOUTH 140+/- CENTERLINE PI OF ROADS EAST AND SOUTH

Signed by *Timothy L. Lapham*

Date 12/25/94

Surveyor's Michigan License No. 27595