

**SURVEY &
REMONUMENTATION**

MAY 0 8 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
OGEMAW

(County)

Located In:

Corner Code #

- | | | | | |
|---------------------------------------|---|-------------|-----------|----------------|
| 1. Public Land Survey | T | <u>23</u> N | <u>3E</u> | <u>M-5</u> |
| | T | ___ | R ___ | ___ |
| | T | ___ | R ___ | ___ |
| | T | ___ | R ___ | ___ |
| 2. Property Controlling
in Section | S | ___ | T ___ | <u>Seg. #1</u> |
| | S | ___ | T ___ | ___ |
| 3. Miscellaneous
Property in Sec. | S | ___ | T ___ | ___ |
| | S | ___ | T ___ | ___ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER **2** PAGE **265**

STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

3 JAN 95 9:36 A.M.

WANDA MUZIK
Register of Deeds Stamp # 109

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
**M-5: CLASON 1838, SET POST, HEMLOCK 12" S24-1/2W 31L., Y. PINE 12" N13-1/2W 49L.
 HIGGINS 6/03/1977, SURVEY #77052 UNRECORDED, FOUND IRON & CAP, 3 WITNESSES
 KING 10/30/1986, SURVEY 4-68, FOUND IRON AND CAP #12018, 4 WITNESSES
 KING 9/9/1991, SURVEY 5-428, REVISION TO SURVEY 4-68, NO CHANGE IN CORNER**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
**M-5: FOUND 1/2" IRON, 1 WITNESS OF 1977 SURVEY, AND 4 WITNESSES OF 1986 SURVEY, 3 WITNESSES CHECK PER RECORD BUT 4TH IS OFF, PROBABLE TRANSCRIPTION ERROR; CORNER POSITION MATCHES SWAMP CALL TO NORTH; CORNER POSITION MATCHES ROAD AND FENCE LOCATIONS ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994.
 SEE REMONUMENTION DOSSIER FOR ADDITIONAL INFORMATION.**

APPROVED BY
PEER REVIEW
TL
DATE 12-21-94 P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
**M-5: SET 5/8"x36" REBOD WITH 3-1/4" ALUMINUM REMON CAP
 N48E 36.81 FOUND NAIL IN FENCE POST
 S88E 27.13 FOUND NAIL IN FENCE CORNER POST
 S27E 48.79 FOUND NAIL IN SOUTH GATE POST
 S70W 35.59 FOUND NAIL IN CEDAR POST**



Signed by *Timothy L. Lapham*
 Surveyor's Michigan License No. 27595

Date 12/29/94