

**SURVEY &
REMONUMENTATION**

MAY 03 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
OGEMAW

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|----------------|
| 1. Public Land Survey | T | <u>23N</u> | R | <u>3E</u> | <u>M-9</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | <u>leg. #1</u> |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER

2 PAGE **268**
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

3 JAN 95 9:38 A.M.

WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9: CLASON 1838, SET POST, HEMLOCK 15" S40W 24L., HEMLOCK 12" N17W 23L.
HIGGINS SURVEY 2-467, 6-08-1978, FD IRON AND CAP, NO WITS
KING SURVEY 4-65*72, 10/30/1986, FD 1/2" IRON, 4 WITS
KING SURVEY 5-128*136, 9/09/1991, REVISION OF 4-65*72 (NO CORNER CHANGE)
KING LCRC 2-127, 9/09/1991, SAME AS 4-65*72
GRANGER SURVEY 5-385*6, FD 1/2" BAR AND CAP, 4 WITS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9: NO EVIDENCE OF GLO CORNER FOUND, FOUND 1/2" CAPPED REROD MATCHING KING AND GRANGER WITNESSES
ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER
CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY PEER REVIEW	
12-21-94	<i>ML</i>
DATE	P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX
N44E 50.05' NAIL IN SE FACE OF POWER POLE
S62E 111.75' NAIL IN POWER POLE
S32W 52.99' NAIL IN POWER POLE
N44W 59.22' SE CORNER FOUNDATION
1.4' NORTH TO CENTERLINE OF EAST-WEST ROAD
0.3' EAST CENTERLINE OF PAVED ROAD SOUTH

Signed by

Timothy L. Lapham

Date

12/29/94

Surveyor's Michigan License No. 27595

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

