

SURVEY & REMONUMENTATION

MAY 03 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OGEMAW **COMMISSION**
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>3E</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **2** PAGE **271**
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED

3 JAN 95 9:39 A.M.

WANDA MUZIK
REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-13: GLO CLASON, 1846 SET POST,

LEANING HEMLOCK 7" N68E 11LKS,
CEDAR 24" N26W 47LKS;

CALDWELL SURVEYS 1-98 NOV 1971, 1-172 MAY 1972, 1-368 JAN 1974, 1-485 MAY 1974, 1-527 OC 1974, 1-483 JULY 1974, NO COR MAT, NO WITS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13: FOUND UNLEGIBLE CAPPED IRON, RECORDED AND ACCEPTED AS CORNER, DISTANCE WEST AND EAST AG WITH GLO

ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

CORNER APPROVED AT PEER REVIEW MEETING HELD DECEMBER 21, 1994

SEE DOSSIER FOR ADDITIONAL INFORMATION


APPROVED BY
PEER REVIEW

12-21-94 TL

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-13: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MON BOX

- N53E 44.43' SET NAIL IN POWER POLE
- S55E 53.81' CENTER OF TELEPHONE PEDESTAL
- S54W 44.50' SET NAIL IN POWER POLE
- N37W 48.77' SET NAIL IN 4X4 POST



Signed by *Timothy L. Lapham*
Surveyor's Michigan License No. 27595

Date 12/25/94