

SURVEY & REMONUMENTATION

MAY 03 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OGEMAW **COMMISSION**
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>3E</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **2** PAGE **272**
STATE OF MICHIGAN
OGEMAW COUNTY
RECORDED
3 JAN 95 9:39 A.M.
WANDA MUZIK
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-13: GLO CLASON, 1846, SET POST,
HEMLOCK 10' N53E 12L.,
HEMLOCK N56W 14L.
CALDWELL SURVEY 1-436 MAY 1974, NO COR MAT, NO WITS;
KING SURVEY 5-333 JUNE 1993, NO COR MAT, NO WITS


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-13: FOUND 1/2" IRON BAR
CORNER FITS GLO STREAM CALL WEST AND, POSITION OF BROOK EAST ACCORDING TO LONG TIME RESIDENT TESTIFYING AS TO FORMER BROOK POSITION
ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER
CORNER APPROVED AT PEER REVIEW MEETING HELD ON DECEMBER 21, 1994
SEE DOSSIER FOR ADDITIONAL INFORMATION

APPROVED BY
PEER REVIEW

12-21-94 *ML*

DATE P.A. 345 of 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-13: SET 5/8"x36" REROD WITH 3-1/4" ALUMINUM OGEMAW REMON CAP IN MONUMENT BOX
N49E 50.84' SET NAIL IN POWER POLE
S29E 80.20' SET NAIL IN 16" W. PINE
S47W 55.70' 1/2" IRON BAR
N25W 61.44' SET NAIL IN 6" ASPEN
EAST 6.76' REMON MONUMENT, D-1 T23N R3E



Signed by *Timothy L. Lapham* Date 12/29/94
Surveyor's Michigan License No. 27595