

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
 REMONUMENTATION  
 MAR 02 2001  
 SECTION

Register of Deeds Stamp & File Number

For corners in

ONTONAGON  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T48N R41W F-1  
 T49N R41W F-13

2. Property Controlling  
 in Section

S T R

3. Miscellaneous  
 Property in Sec.

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 Corner common to Section 4 & 33, T48N T49W, R41W.  
 2000

I, Earl W. Applekamp, in a field survey on June 24, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William A. Burt, U.S. Deputy Surveyor, Summer 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

6" Hemlock N49°E 11 Links ( 7.26 Feet)  
 9" Sugar N28°W 23 Links (15.18 Feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A County Road running East and West turns North at the Corner Position. This road has been in existence since about 1920. I re-established the Corner at the intersection of the center of the East-West and North-South County Road. This position is very close to being on line and equal distance between opposite Section Corners East and West.

Research on file with the Ontonagon County Remonumentation Program Representative.

*Earl W. Applekamp, 7-26-00*  
 COUNTY REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 At the Corner position I set a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, T49N, R41W, 1/4, S4, S33, 2000, P.S. 17610. I established three bearing trees and a reference monument.

Nail in 4" Spruce N24°W 91.84' - Nail in 5" Aspen S77°E 77.55'  
 REF. MON. N55°-14'-52"W 87.31' - Nail in 6" Aspen S14°E 96.06'



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date June 24, 2000