

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ontonagon  
(County)

Located in:                      Corner Code #                     

- |                                    |               |               |                             |
|------------------------------------|---------------|---------------|-----------------------------|
| 1. Public Land Survey              | T <u>52</u> N | R <u>37</u> W | L11                         |
|                                    | T <u>52</u> N | R <u>37</u> W | K12                         |
|                                    | T <u>   </u>  | R <u>   </u>  | <u>                    </u> |
|                                    | T <u>   </u>  | R <u>   </u>  | <u>                    </u> |
| 2. Property Controlling in Section | S <u>   </u>  | T <u>   </u>  | R <u>   </u>                |
|                                    | S <u>   </u>  | T <u>   </u>  | R <u>   </u>                |
| 3. Miscellaneous Property in Sec.  | S <u>   </u>  | T <u>   </u>  | R <u>   </u>                |
|                                    | S <u>   </u>  | T <u>   </u>  | R <u>   </u>                |

Register of Deeds Stamp & File Number

4. Lot No.           , Recorded Plat                       
 5. Private Claims

May 24 2001

I, Stephan J. Szyszkoski, in a field survey on                     , 19    do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11											●	
12	31		32		33		34		35		●	36
13												

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (L11) Quarter corner common to Sections 25-36. 1846: Established by S.W. Higgins. ...39.95 Set 1/4 Sect. post. Sugar 16 N45E 15. Ironwood 10 S20W 20.  
 (K12) Quarter corner common to Sections 35-36. 1846: Established by S.W. Higgins. ...40.00 Set 1/4 Sect. post. Sugar 12 S31W 31, Maple.12 N35E 18.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L11) Original post and accessories were not recovered. Reestablished the corner position on a line of mean true bearing between section corners 2653.18 feet east and west.  
 (K12) The original post and accessories were not recovered. Reestablished the corner position on a line of mean true bearing between Section corners 2687.32' north and south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L11) Set 1" IDx32" iron pipe with 4" alum. MDNR tablet. Blazed and scribed:	(K12) Set 1" IDx32" iron pipe with 4" alum. MDNR tablet. Blazed and scribed:
8" Sugar N80W 18.9' "1/4S NBT"	14" Oak N13E 67.1' "1/4S NBT"
7" Sugar N10W 23.4' do	6" W.Ash S32E 115.8' do
18" Sugar S88E 23.1' do	5" Ironwood N80W 53.3' do
10" Sugar S33W 38.6' do	14" W.Ash North 45.7' do
Set squared cedar post adjacent.	Squared cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.
Bearings are magnetic. Distances to notch in lower blaze.	C/L M26 S30E 37 feet.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/25/01

For the Michigan Department of Natural Resources - Office of Property Management