

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
 (County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section

S 23 T 53N R 38W 2
 S 14 T 53N R 38W WC N. of #16

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

WC May 17 2000
 2 May 01 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 23) East 1/16 between Sections 14-23. Established in 1965 by Billy D. Buckler, RLS. 1" pipe with 4" brass cap. 13" Cedar S11W 32 links, 10" Cedar S79W 53 links.

(WC North of #16, Sec. 14) Witness corner. A point on the east, North-South 1/16 line of Section 14. The 1/16 line was established in 1965 by Billy D. Buckler RLS, at the mean bearing of the N-S 1/4 line, Sec. 14 and the East line of Sec. 14. Buckler placed a 1" pipe with 4" aluminum cap on this line, witnessed by the following: 17" W. Pine N70E 89.5 links, 13" W. Pine N02E 41.5 links. His monument is 1397.22' N. of #16 by the field notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 23) Recovered and accepted the 1965 monument, which is in good condition and at record distance from the 1965 bearings trees. Bearings are several degrees different as noted below. Position checks with corners to east and west.

(WC North of #16, Sec. 14) Buckler's monument and witness trees were not recovered. Reestablished the East, North-South 1/16 line of Sec. 14 according to method employed by Buckler in 1965. Placed a 1" ID x 32" iron pipe with 4" dia. cast aluminum MDNR tablet on the 1/16 line, 1398.50' N 02 deg. 57'10"E (NAD83-1994 adjustment grid bearing) from the East 1/16 corner between Sections 14-23. The monument is about 19' south of the apparent OHWM of Lake Superior. The monument is stamped "Witness Cor. E 1/16 line Sec. 14 PS33986 5-16-00"


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2-Sec. 23) Found 1" pipe with 4" brass cap. Blazed and scribed the following bearing trees:

12" Y. Birch N04W 37.0' "1/16S BT"
 11" Cedar S89E 38.2' do
 The 1965 wits:
 15" Cedar N21W 21.4' scribing visible
 13" Cedar S85W 35.4' overgrown blazes.
 Bearings are magnetic. Dist. to notch in lower blaze.

(WC North of #16) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:

7" Cedar S50E 12.3' "WC BT"
 8" Hemlock S50W 24.8' "WC BT"
 10" Hemlock S72W 29.7' "WC BT"
 6" Cedar N64W 21.9' "WC BT"
 Placed a squared cedar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/00

For the Michigan Department of Natural Resources - Forest Management Division