

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>53N</u> R <u>38W</u> | K <u>9</u> |
| | T <u>53N</u> R <u>38W</u> | I <u>8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I8 May 02 2000
 K9 May 16 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(K9) Corner common to Sections 23-24-25-26. Established in 1846 by Higgins and Hubbard. "80.00 Set post cor. Secs. 23,24,25,26. Hemlock 30 N65E 11, Spruce 14 S25W 25". Found no subsequent record.

(I8) Quarter corner common to Sections 22-23. Reestablished in 1965 by Billy D. Buckler, RLS. 1" pipe with 4" aluminum cap. 12" Y. Birch East 5.5 links, 18" Soft Maple N35W 12 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) The original post and accessories were not recovered. There are several old hemlock stumps in the area but none will match the record. Reestablished the corner in accord with U.S. record of stream calls to north, south, east, and west, and at record distance from section corner to the north. From the position thus established, I found a wood post, 3/4" iron pipe, and a metal location poster marked "app. sec. cor.", placed by persons unknown and not of record, N67W 91'. At the position for the corner, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

(I8) Recovered and accepted the 1965 monument, which is in good condition and at record distance from the 1965 witness trees, both in good condition. Some variation in bearings observed as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 8" Sugar N67W 16.6' "S23 NBT"
 7" Maple N26E 10.6' "S24 NBT"
 7" Maple S81E 9.4' "S25 NBT"
 21" Hemlock S44W 25.2' "S26 NBT"
 Bearings are magnetic. Distances to notch in lower blaze.

(I8) Found 1" pipe with 4" alum. cap.
 Blazed and scribed the following new bearing trees:
 7" Cedar S11E 21.7' "1/4S NBT"
 9" Cedar S53W 35.8' do
 The 1965 wits:
 15" Y. Birch S84E 3.5' overgrown blaze
 18" Maple N49W 8.1' do
 Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/00

For the Michigan Department of Natural Resources - Forest Management Division